

AGUA FINITA / THE ENERGY LANDSCAPE AND THE CITY

V12 spatial control / full issued territory with a production enlargement / source terrain, no vertical exaggeration



PRODUCTION INTERFACE / ENLARGED




PV extensions + crop operations
Shared power / cooling plots + modular compute halls
Repair workshops + separate service access

Z1 Southwest city + production Z2 Agricultural research
Z3 Energy / solar-agricultural opportunity
Z4 Production + transfer Z5 Gateway Z6 Mountain stewardship

Olive fields are resource-gated long-term agrivoltaic proposals, not completed arrays. Gold outlines identify fixed pilots without replacing their internal layout. Individual buildings are small at territorial scale. The inset uses a flat working datum; terrain fit and equipment engineering remain open.

AGUA FINITA / FIELDS FOLLOW THE GROUND

V12 whole-territory design study / conditional agrivoltaic extension, source channels and issued site boundary




CONTINUITY WITH REASONS


Olive / future field footprints
Gold / protected fixed pilots
Blue / source seasonal channels
Dashed / proposed regional roads
Dark outline / issued site boundary


Channels break the field pattern.
Steeper ground stays outside
this production layout.
Service lanes separate work blocks.


Future fields are not installed PV.
Water, power and market gates
control actual construction.

Design assumptions: 1,200 x 600 m working blocks, 12 m edge strips, p95 slope <= 5%, 150 m channel screening corridor. These are not statutory standards.
Field footprints are clipped to the current issued boundary and avoid protected pilots. Existing pilot interiors are neither inferred nor replaced.


N
Z2
AGRICULTURE RESEARCH
Z3
ENERGY RESEARCH
Z4
PRODUCTION + TRANSFER
Z5
GATEWAY + LOGISTICS
Z6
MOUNTAIN STEWARDSHIP
Z1
URBAN + SERVICES
10 km


N
NORTH
LIVING PRECINCT
D
S
S
C03 / DRY-WASH
LANDSCAPE PARK
SOUTHEAST
LIVING PRECINCT
S
S
SOUTHWEST
LIVING PRECINCT
C / PUBLIC CENTRE
0.5 km


N
BUS + SECONDARY
STREET SPINE
D
S
D
S
S
D
FREIGHT SERVES P
IN A SEPARATE INSET
MAIN PASSENGER ARRIVAL
0.5 km


N
PROPOSED SHADE
AND WALK LINKS
SEASONAL WASH
LANDSCAPE STUDY
DRY PARKS +
TARGETED PLANTING
0.5 km

Compute halls: compact work, shared infrastructure

Eight existing hall footprints and the declared 2 / 4 / 8 MW IT scenario retained. No new installed capacity is claimed.



SPATIAL DECISIONS

Separate halls; shared services.

Short internal service loop.

Repair lies north on the freight spine. See overall plan.

Utility plots are protected from building encroachment.


No residential heat demand is invented to justify proximity.

Concept dimensions: 96 x 48 m halls; 36 m lateral gaps and 72 m between rows. These are design assumptions, not fire or vendor standards. Plant footprints reserve space, not equipment sizing. Verify cooling, electrical separation, lifting, turning and terrain before fixing the layout.

Construction phases: operate before expanding


One coordinated layout. Colour shows active halls; outlines show later works. Plant and access must be commissioned before IT starts.

PHASE 1 / 2 MW IT scenario




Commission access, power, cooling and two isolated halls.

PHASE 2 / 4 MW IT scenario



Add two halls after utility headroom, customer demand and resources.

PHASE 3 / 8 MW IT scenario




Add the second four-hall row; retain construction separation.

Retained IT values are declared design scenarios, not power-block ratings. Equipment configuration, peak site demand, interconnection and water rights remain unresolved.

Agrivoltaics: panels, crops and working space together

Proposed-extension prototype only. Existing pilot interiors remain unchanged. Dimensions below are declared design assumptions.



CULTIVATION + OPERATIONS


Blue bands: photovoltaic row envelopes.
Green ground: forage strips.
Circles: pruned jojoba scenario below alternate panel rows.
Sand: separate working lanes / headlands.
Dashed: zoned irrigation service.

Final crop mix, male/female layout, clearances and irrigation follow agronomy and equipment verification. Drought tolerance is not zero demand.

Assumed 4 m panel envelope + 8 m forage/worked ground + 6 m service lane. Under-panel forage and jojoba both remain production uses.
Planting circles illustrate mature/pruned working envelopes; they are not a verified yield, plant-density or pollination design.


Section: keep cultivation and maintenance possible

Extension study, not an approved mounting system. The fixed pilot is not redesigned by this section.



Test before fixing dimensions

Panel motion / structural depth; mature plant height and wind pollination; maintenance vehicles, safe working clearances, pruning and harvest; irrigation and drainage; electrical isolation. Do not infer an engineering clearance from the illustrated gap.


N
A03
E
0.1 km

C03

